

Analysis Results of Rainwater Obtained Inside the Dike at the Tank Area After Treated by the Rainwater Treatment System

<Desalination RO membrane system>

	Radioactive density [Bq/L]		Sampling place	Sampling date	Sampling time
	Chemical Analysis Building *	Laboratory at Unit 5 and 6			
Cs-134	ND (7.6E-01)	/	Treated water tank	June 16, 2014	2:00 PM
Cs-137	ND (7.5E-01)				
Gross β	ND (4.7E+00)				
Tritium	ND (1.6E+02)		Receiving tank	Jun 12, 2014	11:00 AM
Notification density rate	0.18				

* "ND" indicates that the measurement result is below the detection limit, and the detection limit of each nuclide is provided in parentheses.

* Analysis of tritium is performed at Environment Management Building.